

BEDFORD TOWNSHIP ROAD COMMITTEE UPDATE - July 18, 2017

The Bedford Township Road Committee, working in conjunction with the Monroe County Road Commission and township engineering consultants, Mannik & Smith Group, have signed contracts for the following road maintenance & improvement projects - planned for completion during 2017-2018 season:

Project #	Project Description	<u>ROAD MAINTENANCE & IMPROVEMENT CONTRACTS WITH MCRC</u>		<u>2017 - 2018</u>		<u>(7/18/17)</u>
		TWP	MCRC	TWP	MCRC	TOTAL
<u>PRIMARY ROAD PROJECTS</u>						
1	JACKMAN RD. - Sterns to Dean Deep strength patching, 2" HMA , shoulders	1.00 mile	\$ 129,876	\$ 43,292	\$	173,168
2	SMITH RD. - Lewis to US - 24 (Telegraph) Deep strength patching, 2" HMA surface, : (excl.drainage)	1.00 mile	\$ 147,747	\$ 120,883	\$	268,630
TOTAL PRIMARY ROAD PROJECTS			\$ 277,623	\$ 164,175	\$	441,798
<u>LOCAL ROAD PROJECTS</u>						
3	DEAN RD. - Crabb to Minx Overband crack fill (OBC)	1.00 mile	\$ 3,188	\$ 1,062	\$	4,250
4	DOUGLAS RD. - Temperance to Erie Base stabilization, HMA 1.75" + 1.50"	.99 mile	\$ 228,440	\$ 76,146	\$	304,586
5	PIEHL RD. - Summerfield to W. Twp. line Base stabilization, double chip seal	.24 mile	\$ 72,615	\$ -	\$	72,615
6	SAMARIA RD. - Secor to W. Twp line Overband crack fill (OBC)	1.05 mile	\$ 3,825	\$ 1,275	\$	5,100
7	SCHOOL RD. - Secor to W. Twp. line Base stabilization, double chip seal	1.00 mile	\$ 251,220	\$ -	\$	251,220
8	DUST CONTROL - 2 applications Calcium Chloride 38%, 2,000 gal/mile	13.75 mi	\$ 39,288	\$ -	\$	39,288
9	MOWING - 3 Cuts Spring: to center of ditch; Summer: back of ditch; Fall: both sides of ditch		\$ 23,600	\$ -	\$	23,600
10	CRABB RD. - Sterns Rd. to US24 Base stabilization, MHA 1.5" + 1.5"	.91 mile	\$ 280,000	\$ -	\$	280,000
TOTAL LOCAL ROAD PROJECTS			\$ 902,176	\$ 78,483	\$	980,659
GRAND TOTAL PROJECTS		2017-2018	\$ 1,179,799	\$ 242,658	\$	1,422,957